




# SINGLE FAMILY RESIDENTIAL DRIVEWAY STANDARDS

## NOTES

1. CONCRETE DRIVEWAY APRONS AND SIDEWALK CROSSINGS SHALL BE CONSTRUCTED OF CEMENT CONCRETE PAVEMENT (3000 PSI), 6" THICK REINFORCED WITH 6" X 6" #10/#10 WELDED WIRE FABRIC (2" MINIMUM COVER FROM THE BOTTOM).
2. FIBER MESH CONCRETE 3000 PSI (MIN.) MAY BE USED IN PLACE OF THE REQUIREMENTS OF NO. 1 ABOVE.
3. CONSTRUCTION OF DRIVEWAY APRON AND SIDEWALK CROSS SLOPE THROUGH THE DRIVEWAY SHALL COMPLY WITH FDOT INDEX No. 515 (SHEETS 3 & 4 OF 6) FOR ADA REQUIREMENTS.
4. REMOVE TREE ROOTS WITHIN 10" OF PROPOSED GRADE.
5. WHEN THERE IS EXISTING SIDEWALK CROSSING THE PROPOSED DRIVEWAY IT MUST BE REMOVED TO THE NEAREST JOINT BEYOND THE DRIVEWAY. THE REPLACEMENT OR NEW SIDEWALK TO CROSS THE PROPOSED DRIVEWAY MUST BE CONSTRUCTED AS PER ABOVE NOTES 1 THRU 3 ABOVE.
6. SIDEWALKS ADJACENT TO LOT PROPERTY LINES CANNOT HAVE A CROSS SLOPE GREATER THAN 2% PER FDOT INDEX 310.
7. CORNER LOTS INVOLVING HANDICAP RAMPS SHALL BE IN ACCORDANCE WITH FDOT INDEX 304 FOR SIDEWALK AND RAMP CONSTRUCTION.



DEPARTMENT OF PUBLIC WORKS  
PINELLAS COUNTY, FLORIDA

## CONCRETE DRIVEWAY APRON

DATE	SHEET	INDEX No.
	1 of 1	